







### Verriere Pare Flamme ( E )




	N° PV		date de validé	Serie	VITRAGE
30min	<a href="#">13 A 457</a>		20/08/2108	<a href="#">MULTIOP 60</a>	PILKINGTON



### Fixes Pare Flamme ( E )









	N° PV		date de validé	Serie	VITRAGE
30min	<a href="#">11 A 722</a>		26/03/2107	<a href="#">40,50,60,80 standard</a>	PILKINGTON
	<a href="#">EFR-14-002862</a>		02/02/2020	<a href="#">Hermetic 55</a>	
	<a href="#">13 A 391</a>		19/08/2018	<a href="#">Hermetic 70 FP E130</a>	AGC
	<a href="#">EFR-15-001919</a>		05/09/2021	<a href="#">Hermetic 55</a>	
	<a href="#">EFR-15-003231</a>		11/12/2022	<a href="#">Hermetic 55</a>	
60min	<a href="#">13 A 393</a>		27/08/2018	<a href="#">Hermetic 70 FP E130</a>	VETROTECH
	<a href="#">EFR-14-002862</a>		02/02/2020	<a href="#">Hermetic 55</a>	PILKINGTON
	<a href="#">EFR-15-003231</a>		11/12/2022	<a href="#">Hermetic 55</a>	VETROTECH




### Ouvrant de service Pare Flamme ( E )











	N° PV		date de validé	Serie	VITRAGE
30min	<a href="#">08 V 156</a>		19/05/2018	<a href="#">Fineline</a>	PILKINGTON
	<a href="#">13 A 392</a>		19/08/2018	<a href="#">Hermetic 70 FP E130</a>	
	<a href="#">EFR-14-002863</a>		11/03/2020	<a href="#">Hermetic 55</a>	









Porte 1 vantail Pare Flamme ( E )					
 <span style="float: right;">Tôle à 100%</span>					
	N° PV		date de validé	Serie	VITRAGE
30min	<a href="#">13 A 392</a>		19/08/2018	<a href="#">Hermetic 70 FP EI30</a>	PILKINGTON
	<a href="#">EFR-14-002863</a>		11/03/2020	<a href="#">Hermetic 55</a>	
	<a href="#">EFR-15-001920</a>		05/09/2021	<a href="#">Hermetic 55</a>	AGC
	<a href="#">EFR-15-003233</a>		11/12/2022	<a href="#">Hermetic 55</a>	VETROTECH
	<a href="#">13 A 394</a>		27/08/2018	<a href="#">Hermetic 70 FP EI30</a>	
60min	<a href="#">EFR-14-002863</a>		11/03/2020	<a href="#">Hermetic 55</a>	PILKINGTON
	<a href="#">EFR-15-003233</a>		11/12/2022	<a href="#">Hermetic 55</a>	VETROTECH

Porte 2 vantaux Pare Flamme ( E )					
 <span style="float: right;">Tôle à 100%</span>					
	N° PV		date de validé	Serie	VITRAGE
30min	<a href="#">13 A 392</a>		19/08/2018	<a href="#">Hermetic 70 FP EI30</a>	PILKINGTON
	<a href="#">EFR-14-002863</a>		11/03/2020	<a href="#">Hermetic 55</a>	
	<a href="#">EFR-15-001920</a>		30/09/2021	<a href="#">Hermetic 55</a>	AGC
	<a href="#">EFR-15-003233</a>		11/12/2022	<a href="#">Hermetic 55</a>	VETROTECH
	<a href="#">13 A 394</a>		27/08/2018	<a href="#">Hermetic 70 FP EI30</a>	
60min	<a href="#">EFR-14-002863</a>		11/03/2020	<a href="#">Hermetic 55</a>	PILKINGTON
	<a href="#">EFR-15-003233</a>		11/12/2022	<a href="#">Hermetic 55</a>	VETROTECH


Mur rideau Pare Flamme ( E )					
 <span style="float: right;">H max entre dalles ≤ 5m</span>					
	N° PV		date de validé	Serie	VITRAGE
30min	<a href="#">09 A 183</a>		20/07/2019	<a href="#">Isofine 45 &amp; Isofine 60</a>	VETROTECH
	<a href="#">13 A 444</a>		05/08/2020	<a href="#">Isofine 45</a>	PYROGUARD
60min	<a href="#">09 A 183</a>		20/07/2019	<a href="#">Isofine 45 &amp; Isofine 60</a>	VETROTECH
	<a href="#">13 A 444</a>		05/08/2020	<a href="#">Isofine 45</a>	PYROGUARD

Fixes Coupe Feu ( EI )					
					
	N° PV		date de validé	Serie	VITRAGE
30min	<a href="#">13 A 391</a>		19/08/2018	<a href="#">Hermetic 70 FP EI30</a>	PILKINGTON
	<a href="#">13 A 752</a>		16/09/2018		AGC
	<a href="#">13 A 393</a>		27/08/2018		VETROTECH
60min	<a href="#">13 A 185</a>		20/08/2018	<a href="#">Hermetic 70 FP EI60-90</a>	PILKINGTON
	<a href="#">13 A 750</a>		12/12/2018		AGC
	<a href="#">EFR-15-000612</a>		05/10/2020		VETROTECH
90min	<a href="#">13 A 395</a>		27/08/2018	<a href="#">Hermetic 70 FP EI60-90</a>	PILKINGTON
120min	<a href="#">13 A 422</a>		20/11/2018	<a href="#">ISO FEU 90/120</a>	PYROGUARD



Fixes Bord à Bord Coupe Feu ( EI )					
  					
	N° PV		date de validé	Serie	VITRAGE
30min	<a href="#">13 A 841</a>		26/11/2019	<a href="#">Hermetic 70 FP EI30</a>	AGC
	<a href="#">13 A 839</a>		03/02/2020		VETROTECH
60min	<a href="#">13 A 840</a>		26/11/2019	<a href="#">Hermetic 70 FP EI60-90</a>	AGC
	<a href="#">13 A 838</a>		03/02/2020		VETROTECH

Porte 1 vantail Coupe Feu ( EI )					
     					
Tôle à 100% sauf en EI90					
	N° PV		date de validé	Serie	VITRAGE
30min	<a href="#">13 A 392</a>		19/08/2018	<a href="#">Hermetic 70 FP EI30</a>	PILKINGTON
	<a href="#">13 A 753</a>		16/12/2018		AGC
	<a href="#">13 A 394</a>		27/08/2018		VETROTECH
60min	<a href="#">13 A 186</a>		20/08/2018	<a href="#">Hermetic 70 FP EI60-90</a>	PILKINGTON
	<a href="#">13 A 751</a>		12/12/2018		AGC
	<a href="#">EFR-15-000613</a>		05/10/2018		VETROTECH
90min	<a href="#">13 A 396</a>		27/08/2018	<a href="#">Hermetic 70 FP EI60-90</a>	PILKINGTON




## Porte 2 vantaux Coupe Feu ( EI )





Tôle à 100%  
avec Smaxi par  
panneau = 1,35m<sup>2</sup>  
sauf en EI90

	N° PV		date de validé	Serie	VITRAGE
30min	<a href="#">13 A 392</a>		19/08/2018	<a href="#">Hermetic 70 FP EI30</a>	PILKINGTON
	<a href="#">13 A 753</a>		16/12/2018		AGC
	<a href="#">13 A 394</a>		27/08/2018		VETROTECH
60min	<a href="#">13 A 186</a>		20/08/2018	<a href="#">Hermetic 70 FP EI60-90</a>	PILKINGTON
	<a href="#">13 A 751</a>		12/12/2018		AGC
	<a href="#">EFR-15-000613</a>		05/10/2018		VETROTECH
90min	<a href="#">13 A 396</a>		27/08/2018	<a href="#">Hermetic 70 FP EI60-90</a>	PILKINGTON

## Mur rideau Coupe Feu ( EI )



H max entre dalles ≤ 5m

	N° PV		date de validé	Serie	VITRAGE
30min	<a href="#">09 A 183</a>		20/07/2019	<a href="#">Isofine 45 &amp; Isofine 60</a>	VETROTECH
	<a href="#">13 A 444</a>		05/08/2020	<a href="#">Isofine 45</a>	PYROGUARD
60min	<a href="#">09 A 183</a>		20/07/2019	<a href="#">Isofine 45 &amp; Isofine 60</a>	VETROTECH
	<a href="#">13 A 425</a>		26/03/2020	<a href="#">Isofine 60</a>	PYROGUARD